GST No. 08ACSPG2733N1Z4 Mb.9828135589

AN ISO 9001 : 2015 CERTIFIED COMPANY

Advanced Techno Engineers

F-47 , Kuber Industrial Area Ranpur, Kota - Rajasthan

Email : ate.msg@gmail.com , info@salvitas.in Website : www.salvitas.in

Dated : 03 24-04-2025

To,

NHIT Western Projects Ltd

Assam

Sub : Quotation of Toll Rate Boards

Dear Sir,

We have pleasure to offer our rates for Supply of safety Items as below:

BoQ for Toll Plaza Fee Board replacement at 02 locations in

ESTIMATED ON THE BASIS OF WORK ORDER RATE (A3) OF RM WORKS

S. No.	Item Description	Unit	Qty	Rate	Amount
1	Providing And Fixing Retro-Reflective Acp Sheeting As Per IRC 67-2022, Utilizing Type Xi Diamond Grade Sheeting (Dg3) With Electronic Cuttable Film (Ecf) Lettering. The Sheeting Shall Be Of Specified Colour As Per Irc 67-2022, With Pressure-Sensitive Or Heat-Activated Adhesive For Secure Installation On Surfaces. The Cut-Out Border Shall Conform To Specified Retro-Reflective Colours As Per Irc 67-2022, Ensuring Clear Visibility For Road Users. The Retro-Reflective Sheeting Must Meet Durability, Reflectivity, And Weather Resistance Standards As Defined In Irc 67-2022. The Application Will Include Surface Preparation, Proper Alignment, And Secure Attachment, Ensuring Uniform Adhesion Without Air Pockets Or Misalignment. The Work Shall Be Includes1 Coat Primer & 2 Coat Painting Of Existing Steel Structure After Removeing Of Rust From Existing Structure. All Work Must Comply With The Instructions And Specifications Of The Engineer-Incharge. The Cost Includes All Materials, Labour, Tools, Equipment, And Safety Precautions For Proper Installation And Finishing. Make: 3M, Or Equivalent As Approved By The Engineer	Sqm	300.00	7150	21,45,000

Terms & Conditions :

1 Taxes : GST -18% Extra

2 Prices are Ex- Works

3 Payment -100 % Advance – 50% advance, 50% after Completion

4 Goods Sold will not be taken back.

5 Rates Only For Supply

6 Inspection at our Site Ex Fac - Kota

NOTE : HYDRA for fixing signages is provided by NHIT

Thanking You,

Yours Truly,

FOR Advanced Techno Engineers

Auothorised Signatory