Work Order

NHIT Eastern Projects Private Limited G-5 & 6, Road Number 224, Sector 10 Dwarka, New Delhi, South West Delhi, Delhi, Delhi - 110075, India, GST - 07AAICN8178R1ZD Company's CIN : U42101DL2023PTC412707	**Work Order No:** WO/FY25-26/126	**Date :** 19-11-2025 Completion Date :19-12-2025
Vendor : A.K.Group (SGV549) Guwahati, Assam, India, 781022 GSTIN: 18AHYPH6191G1ZP PAN : AHYPH6191G Email : groupak491@gmail.com Mobile : 8134040915	**Custom Ship Location Name** NHIT Eastern Projects Private Limited KPRP-Cap - Ops(000006003) Galia, Patacharkuchi Pathsala - 781326	

Subject :

New Construction of Porta Cabin foundation work

Reference :

PR/NOV25/045

Dear Sir :

With reference to the offer submitted and subsequent discussion regarding New Construction of Porta Cabin foundation work at Galia Toll Plaza, Kaljhar-Patachakuchi Assam Toll Road Highways Project. We are pleased to issue this Work Order, as per detailed terms and conditions mentioned below.

Key Terms & Conditions :

Title	**Description**	
Brief Scope of Work.	Construction of new Porta Cabin foundation work at Galia Toll Plaza, Kaljhar- Patachakuchi Assam Toll Road Highways Project. The Detailed Bill of Quantity is attached as **Annexure B**	
Time for completion.	Within 30 Days from the Time of Mobilization.	
Time for Mobilization	Within 10 days from the issuance of work order.	
Contract Price.	**Rs. 2,47,015.94/-** (Excluding GST)	
Advance Payment.	NIL	
Performance Security.	NIL	
Liquidated Damages.	0.5%-Max up to 10% (Ten Percent) of the work order value.	
Retention Money.	NIL	
Payment of the certificated interims/Final Bills.	Payment shall be made after Completion of work and submission of invoice within 45 days. Invoice should be duly approved by Project Manager. In addition to submission of hard copies of invoices at site, Vendors are required to Email their invoices along with accepted copy of WO/LoA on ***invoices@nhit.co.in.***	
Defect Liability Period.	3 Months from the date of Completion of works.	
	Employer	**Contractor**
Authorised Contract Person	**For Works.**	**M/s A.K.Group**

AMS
Forum

	Maintenance Manager: Mr C Mahesh **Contact No: 9500933097** **Email Id: cmahesh@nhit.co.in**	Authorised person Contact No-9706346509 Email id- info@akgroup.co.in

Annexure - A (General Terms And Conditions) :

1. SCOPE OF WORK:

1.1 The Scope of Work shall include all item specified in the BOQ including supply of all materials, equipment, Labour, Plant and machinery, tool & tackles required for the work, unless otherwise specifically mentioned to the contrary elsewhere in this contract.

1.2 Any incidental work not particularly specified in the specifications but required to complete the works shall be contractor's responsibility at no extra cost to the employer.

1.3 The Contractor shall be responsible for all activities required for the works at site and any damage caused to existing facilities/ adjacent works within the project site during execution of work shall be made good by the contractor at its own cost and expenses.

1.4 The scope of work is not limited to the bill of quantities, it may be supplemented/ added/deleted by the authorized representative of the Employer, considering overall project requirements and MoRTH Specification and Item Specification the Contractor. However, the decision of the Employer shall be final and binding on the contractor.

1.5 Contractor will not be permitted to sublet the work mentioned in this work order to anyone else without prior written approval of the Employer's Authorised Representative. The security of Contractor's materials as well as the materials, if any issued to Contractor by the Employer will be Contractor's responsibility. In case of any loss of Employer's material the same shall be recovered Contractor's bills.

1.6 Contractor will carry out the work as per the discussions and instructions of the Authorised Representative of Employer or Authorised Representative of Employer from time to time. The contractor shall maintain instruction book at site. The instructions / comments received from the Authorised Representative of Employer of Employer/ Authority should be complied forthwith and immediate remedial actions taken by Contractor should also be noted therein & shown to Authorised Representative of Employer.

1.7 All costs towards transport, handling, hoisting, storage, watch and ward for all the materials procured for use in the Works, including all the equipment, labour, machinery, tools and tackles required for the Works as per needs from time to time shall be included in the Quoted Price and no extra claim on account of these charges will be entertained.

2. Contract Price:

2.1 The Rate Mention in the BOQ shall inclusive of duties to be paid to appropriate competent authorities arising out contractor's work and contractor's overhead and profit. It is Contractor's responsibility to make all necessary inquiries in this respect and its shall be deemed to have satisfied himself regarding the applicable of all relevant tax laws.

2.2 The Contractor has to make its own arrangement for the accommodation/ transportation of its workforce, water, electricity and no extra cost will be payable in this regard.

2.3 The rate shall remain firm and shall not be subjected to any revision / variation / escalation, until completion of the entire job. No idle / detention charges shall be payable in any circumstances.

2.4 No adjustments in Contract Price are entitled due to fluctuations of market, prices of labour/material/P&M, unless provided in the contract. Also, BoQ rate said to be final and not subject to any escalation or variation till the completion including extensions.

2.5 The rate of all BOQ items is inclusive of all taxes, duties, labour Cess, Wastages, insurance, royalties, transportation, loading & unloading etc except GST. The rate shall be valid for any variation in quantity & shall be valid for all leads and lifts. The rates shall also include & provide for timely execution of all necessary preliminary works, enabling works and allied works related to Contractor's scope of work. GST will be paid separately as per prevalent rates in force from time to time.

3. Time of Completion:

3.1 The contractor shall finalize the programme with the Employer and according to the programme mobilized the resources viz. manpower and machinery etc.

3.2 The contractor shall have the option to work through night, after obtaining special approval from Employer and on locally recognized holidays, days of rest and the contractor shall make suitable arrangement for the same, at no extra cost to the Employer.

3.3 The completion time includes weekly reast days, official holidays, and days of inclement weather.

3.4 The Contractor shall ensure that, all applicable permission and approvals form competent Governmental authorities are taken by him.

3.5 The work shall be deemed to have been completed in accordance with this contract and relevant specifications and to the satisfaction of the Employer only upon issuance of the taking over Certificates by Employer to the contractor.

3.6 The time of completion may be extended at the sole discretion of the Employer, if the progress of work is delayed for any reason which is beyond the reasonable control of the contractor and not attributable to the contractor.

3.7 If the contractor considers himself to be entitled to any extension of the Time of Competition in accordance with the provisions of this contract, the contractor shall give notice to the Employer authorised representative describing the delay event along with relevant supporting documents. The notice shall be given not later than 7 days after the contractor become aware or should have become aware of such delay event. If the contractor fails to give notice within such period of 7 days, the time of completion shall not be extended.

4. Liquidated Damages:

4.1 It is expressly stipulated that time is the essence of this work order. The work has to be satisfactorily completed in the specified time from the date of this work order which is being accepted and acknowledged by Contractor. If contractor fails to complete the work even after 10 days after end of contract period, the balance work will be carried out at the risk and cost of the Contractor. The LD to be imposed shall be as mentioned in the Key Terms and Conditions.

4.2 In the event of non-payment of liquidated damages as stipulated herein, the Employer shall be entitled to levy an interest @18% till dated of realization of liquidated damages, the said sum shall be payable by sole fact of the delay without the need for any previous notice or any legal proceedings, of proof of damages, which shall in all cases be considered as ascertained. The Employer may, without prejudice to any other method of recovery, deduct the amount of such liquidated damages form any moneys in its hand due to which may become due to the contractor. The payment of deduction of such damages shall not relieve the contractor for its obligation to complete the work or form any other of its obligations and liabilities under the contract.

4.3 In the event, the contractor abandons the jobs in an incomplete manner, the contractor waives his right for reimbursement of amount deducted from the interim bills towards retention money till date.

5. Advance Payment: NA

6. Performance Security: NA

7. Retention money: (If Applicable, as mentioned in Key Terms and Conditions)

For every payment for works due to the contractor in accordance with the work order, the Employer shall deduct 5% (five percentage) thereof as guaranteed money for performance of the obligations of the contractor during the construction period (the **"retention money"**) subject to the condition that the maximum amount of retention money shall not exceed 5% (five percentage) of the work order value.

Upon Occurence of the Contractor Defect:- With in 15 days of the date of Defect liability period, the Employer shall refund the retention money to the contractor.

In the event termination of this Work order, the contractor waives his right for reimbursement of amount deducted from the interim bills towards retention money till date.

8. Defect liability period: (If Applicable, as mentioned in Key Terms and Conditions)

The contractor shall be responsible for all the defects and deficiencies, except usual wear and tear in the work allocated in this work order, till the expiry of a period as mentioned in the Key Terms and Conditions commencing from the date of taking over certificate issued by the Employer:

The contractor shall repair and rectify all defects and deficiencies observed by the Employer during the defects liability period within 15 days from the date of notice issued by Employer or within such reasonable period as may as determined by the Employer at the request by the contractor, in accordance with good industry practice.

If the contractor fails to repair and rectify such defect and deficiency within the specified as cluse no 8.2, the Employer shall entitle to get the same repaired, rectified or remedied at the contractor's cost. The cost of damages shall be recoverable by Employer from the contractor and may deducted by the Employer from any money due to the contractor.

9.Payment terms (Interim/Final Bills)

9.1 The following details has to be complied for entitlement of bill

Sr.No.	Compliance type	Frequency of submission/ compliance
1	Work done Measurement (as certified by Employer's representative on the day of work)	Monthly
2	GST Registration	One Time
3	GST Return	Monthly
4	MSME Registration	One Time

9.2 The Contractor shall submit the monthly bills in the following manner.

- In soft copy format & hard copy format to Project manager for Employer's certification to the Employer by the 5th of the following month, along with necessary supporting documents such as detailed Measurement etc.
- The certification will be done based on measurement for regular scope of works.
- On failing to submit in the above documents, the respective monthly bills shall be carried forward to the next month and the appropriate payment will be affected.

9.3 Necessary deductions for retention money (as stipulated), TDS and *Advance payment* recovery (as stipulated) has to be deducted in monthly and final bills.

9.4 Payment of the certified interim/final bills shall be made as mentioned below after receipt of invoice along with required backup documents as per provisions under this Clause by the Employer for regular Scope of work. Payment shall be released by Employer within 45 days of receipt of invoice along with required backup documents.

10.Technical Specification, Codes and Standards:

10.1 The Works shall be carried out in accordance with the following:

- All the work shall be carried out as per approved design & drawings and methodology and direction of the Authorised Representative of Employer.
- The work shall confirm to latest Manual of Specifications and standards, relevant codes published by IRC and MoRTH Specifications.
- All material and work shall confirm to BOQ, MoRTH Specifications/other relevant Indian Standards together with their latest revision/amendments as per applicable on the date of accepted offers/as specified by the Employer.
- In the absence of specifications for any particular item or items of work the relevant Indian Roads Congress / Indian Standard (IS) codes of practice, together with their latest revisions / amendments as applicable on the date of the Contractor's offer shall be followed.
- In absence of the relevant IRC / IS codes of practice, the instruction of the Employer shall be final, and the Contractor shall deliver in accordance with the Employer's instructions.
- The Contractor shall ensure to provide the proper concrete mix as represented in BOQ.

11.Contractor's General Obligations/Responsibilities:

11.1 The Contractor hereby site visit that prior to quoting and negotiating the rates to the Employer a complete and careful examination has been carried out by them and made an independent evaluation of the Proposal, Scope of the Project, Specifications and Standards of design, construction and maintenance, Site, local conditions, physical qualities of ground, subsoil and geology, traffic volumes, suitability and availability of access routes to the Site and all information provided by Employer or obtained, procured or gathered otherwise, and has determined to its satisfaction the accuracy or otherwise thereof and the nature and extent of difficulties, risks and hazards as are likely to arise or may be faced by Contractor in the course of performance of your obligations hereunder. Contractors confirm there is no claim whatsoever against the Employer in this regard.

11.2 The Contractor shall submit the full particulars of all Temporary Works including construction of office, labour accommodation, stores, etc to the Employer. The expense for this has to be made by the Contractor. The Temporary works should be maintained and repaired by the Contractor till the completion of Works at their own cost and as per the Employer satisfaction. Also, Contractor should provide water and electric supply to their workmen as to the satisfaction of Employer. Contractor is responsible for all damages to telephone, telegraph and electric cables/wires, sewers, water (or) other pipes and other services, except where the Public Authority (or) Private party owing or responsible for the same elects to make good the damage, for which Contractor has to incur the cost to Public Authority or Private party.

11.3 The Contractor shall execute and complete the Works providing labours, materials and all other things and remedy any defects therein in strict accordance with the Contract, with due care and diligence and to the satisfaction of the Employer, The Contractor shall comply with and adhere strictly to the Employer's instructions and directions on any matter, touching or concerning the Works.

11.4 The Contractor shall take full responsibility for the adequacy, stability and safety of all Site operations and methods of construction.

11.5 The Contractor shall be responsible for the professional and technical competence of his/her/its Employees and will select for work, reliable individuals who will perform effectively in the implementation of the Works, respect local customs and conform to a high standard of moral and ethical conduct.

11.6 It shall be the Contractor's liability & responsibility to provide adequate qualified, skilled & experienced personnel and the requisite machineries, plant, equipment, tools & tackle & other resources to ensure acceptable quality of works & the completion of the works in the specified period only.

11.7 The Contractor shall neither seek nor accept instructions from any authority external to the Employer in connection with the performance of his/her/its Works under this presents. The Contractor shall refrain from any action which may adversely affect the Employer and shall fulfil his/her/its commitments with fullest regard for the interest of the Employer.

11.8 Contractor shall keep the work site always free from encroachments, encumbrances, obstruction, and the site shall always be in good presentable condition.

11.9 Contractor will not be permitted to store / use any hazardous materials anywhere in project site or temporary structure in and around project.

11.10 The site shall be always kept neat & clean throughout the duration of the project at no extra cost to the Employer & on completion of project the site shall be handed over in a clean condition. The Employer reserves the right to do what is necessary to keep the site in neat &clean condition and recover the cost so incurred from Contractor's Bills.

11.11 Clearance of the Project Site during the currency of the works, the contractor shall keep the project site free from all necessary obstructions and shall store or dispose of any contractor's equipment and surplus materials. The contractor shall clear away and remove from the project site any wreckage, rubbish or temporary works no longer required.

11.12 All necessary documents used for performing this Contract shall be treated as confidential and shall be delivered only to the Employer's representative, their contents shall not be known to any person other than personnel of the Contractor performing services under this Contract.

11.13 Neither this Contract nor any of the rights or obligations of the Contractor hereunder may be assigned or transferred without the Employer's prior written consent.

12. Sufficiency of Contract Price:

12.1 The Contractor shall be deemed to have satisfied, inspected and collected the necessary data about nature of land and subsoil, nature of the site, nature of the work and materials necessary for completion of work, means of access to site and the accommodation required, general information which may affect their offer like contingencies, climatic, hydrological, natural conditions and other circumstances himself/herself/itself before submitting the offer as to the correctness and sufficiency of his/her/its offer for the construction of the Works and of the rates and prices, which rates and prices shall, except in so far as it is otherwise provided in this Contract, cover all his/her/its

obligations under the Contract and all matters and things necessary for the proper execution and completion of the Works.

12.2 No claims will be entertained in this connection against the Employer. It is specifically agreed between the Parties that the Contract Price agreed is final and the Contractor cannot seek revision in the Contract Price on account of the factors specified herein. Any failure, non-familiarity, or ignorance in acquaint of any of the factors specified herein, will not relieve the Contractor from the responsibility of successfully performing the Work within the committed target and in no case, it cannot be considered as a reason for claims.

13. Health, safety, and Environment- Rule & Regulations:

13. 1The Contractor shall abide by all safety standards, precautions, specification, and practices in construction as per the agreed safety plan which shall conform to the generally accepted industry standards.

13.2 Contractor is responsible for safety of their Employers and should provide all safety appliances to their employees working in their area of operation at his own cost. In the event of repeated violation of safety rules by any of their workmen, the violator shall not be permitted inside the Site.

13.3 The Contractor shall in connection with the Works provide and maintain at his/her/its own cost all lights, guards, fencing and watching when and where necessary or required by the Employer for the protection of the Works and the materials and equipment utilized there of or for the safety and convenience of the public or others.

13.4 The contractor shall be totally responsible for entire safety of the contractor's labourers, supervisors, and surrounding areas of the Work sites where the contractor works, and contractor will use Safety Items such as Safety Shoes, Safety Belts, Safety Gloves, Helmets, Mask goggles, etc. and various other protective equipment's to ensure that the workers are working under utmost safety conditions and Contractor will ensure the immediate availability of proper & adequate First Aid Facilities to all EmployeES / Workmen employed by yourself at work sites. All accidental charges shall be borne by contractor at no extra cost to the Employer.

13.5 No work is to be left unfinished which is unsafe to road user / unsafe to any man-made structure / unsafe to nature. In case of accident, the contractor is responsible to resolve the issue at his own cost. Rectifying any land slide, flow, collapse, damage etc., during or until the completion of any given section is the responsibility of contractor at his own cost which will be considered incidental to the work.

13.6 The contractor will observe all provisions of Labour Laws / Acts and Rules as applicable to these works and safety rules and regulations of the project and enforce the same on all workmen. The contractor will also be responsible for the good conduct of the workers.

13.7 The contractor shall carry out all the works in such a manner that there is no adverse impact on the natural surroundings and environment. The contractor shall follow the Environmental norms of the Employer.

13.8 The Employer shall not be liable for or in respect of any damages or compensation payable at law in respect or in consequence of any accident or injury to any workman or other person in the employment of the Contractor or any sub-Contractor. The Contractor shall indemnify, hold and save harmless the Employer against all such damages and compensation, save and except as aforesaid, and against all claims, proceedings, costs, charges and expenses whatsoever in respect thereof or in relation thereto.

14. STATUTORY AND LEGAL REQUIREMENTS:

14.1 The payment of workmen shall be done by the Contractor in presence of the representative of the Employer. If a complaint regarding non-payment/ short payments of wages is received by the Employer from any of Contractor's workmen, the Contractor's bill shall be held up until inquiry is completed and once the Employer's representative is satisfied that the workmen's wages shall be deducted from Contractor's bill and paid directly to the workman.

14.2 In case of any complaint regarding non-payment of wages to workers is received; contractor's bill shall be kept under HOLD until completion of inquiry. If Authorised Representative of Employer is convinced that the workmen wages have not been paid, such wages shall be directly paid to the aggrieved worker and shall be recovered from the Contractor's bill with 10% extra towards establishment cost

14.3 The Contractor should comply all applicable Acts as per law. The contractor should submit the proof of evidence to the Employer on its request. No extra cost to be paid for compliance of such laws. The Employer shall be indemnified in case any action is initiated by the authorities for contravention by the Contractor.

15. Termination and Consequences:

15.1 In the event of progress of work is consistently found to be lower than the accepted programme and if the quality of work being executed falls below the expected standards laid down by the Employer, in such cases, in the interest of timely completion of the work and to maintain the high quality of work, the Employer reserves the right to delete any part of the scope of work or entire balance work from the Contractor's scope and get such works executed by other agencies/contractor at the risk, cost and expenses of the Contactor. The Authorised Representative of the Employer may terminate this work order at his discretion by giving written notice of 3(three) days at any time without assigning any reason and without entertaining any claim for labour or material or any other expenses or damages.

15.2 In the event of termination, the Employer shall make the full and final settlement to the Contractor in accordance with the Works for the satisfactory services rendered and items of work completed and for any work in progress till the effective date of termination, provided the Contractor shall deliver the items of work to the satisfaction of the Employer.

16. Resolution of Disputes:

16.1 In case of any claim, disagreement or dispute arising out of, or in connection with this Contract or any breach thereof, the following procedure for resolving such claims, disagreements or disputes shall apply.

16.2 Notification:- The aggrieved Party shall immediately notify the other Party in writing as to the nature of the alleged claim, disagreement, or dispute, not later than seven (7) days from the date of knowledge / awareness of the existence thereof.

16.3 Consultation: - On receipt of the notification provided above, the representatives of either Parties shall commence consultations with a view to reach an amicable

resolution of the claim, disagreement, or dispute without causing any suspension/ interruption of the Works.

16.4 Arbitration: - If the dispute does not get resolved within a maximum period of 15 days from the date of notification, it shall be referred to a sole arbitrator appointed by the Employer. The arbitration shall be conducted in accordance with the provisions of Arbitration and Conciliation Act, 1996 or any statutory modification or reenactment thereto for the time being in force. The Parties shall be bound by the arbitral award rendered in accordance with such arbitration as the final adjudication of any such disagreement, controversy, or claim. The arbitration proceedings shall be held in Delhi only. Language of the arbitration shall be in English, and the cost of the arbitration shall be borne by the respective Party as decided in the arbitral award. The Parties hereto agree that the Courts at Delhi only shall have jurisdiction in respect of all matters whatsoever arising out of this Contract.

17.Indemnification:

The Agency shall hold the Employer harmless and shall indemnify the same against all claims, penalties, fines, losses, damages, costs and proceedings arising from the breach or contravention of any laws, rules and regulations referred to in this order

18. Compliance to Anti-Bribery & Corruption Policy:

The Contractor undertakes to comply with all the applicable Laws/ Statutes/ Directives or Regulations relating to Anti-Bribery Laws in India and shall promptly notify the Employer of any actual or suspected breach and provide all required information in this regard. Upon the occurrence of an actual or suspected breach, the Contractor shall promptly take all remedial actions as suggested by the Employer and in the event of any failure to take such remedial measures by the Contractor this Contract shall be automatically terminated with immediate effect without damages or other sanction.

Detailed BOQ

S.No.	Product Description	Qty	UOM	Unit Price (INR)	Amount	Total Amount
1	Excavation for foundation in earth, soil of all types, sand, gravel, and soft murmur, including removing the excavated material up to a distance of 50m, beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary backfiling, ramming, watering including shoring and strutting etc. all complete.	13.65	cum	390	5,323.50	6,281.74
2	Backfilling of development area of Porta Cabin room for the depth of 2.5m with the approved borrow area material with all leads & lifts, transporting to site, spreading, grading to required slope and compaction to meet the requirement of table 300.2	54	cum	490	26,460.00	31,222.80
3	All charges for supply & placing of Plain Cement Concrete (M-15 grade) in open foundations as per approved drawings and technical specifications, conforming to MoRTH Sections 1500, 1700, and 2200. The concrete shall be batched using a batch mix plant, ensuring uniformity and consistent quality. The mix shall use aggregates of size not exceeding 20 mm, with a workable slump suitable for PCC. The thickness of PCC shall be as specified in drawing. Concrete placement shall ensure a free-fall height of less than 1.5 m to prevent segregation, compacted using mechanical vibrators to achieve proper consolidation. The work	2.29	cum	5200	11,908.00	14,051.44

	includes the preparation of the foundation surface, leveling, placing concrete, and finishing exposed surfaces to achieve the required levels and smoothness. Adequate curing, as per approved methods, shall be carried out for at least 7 days to attain the desired strength. Sampling and testing shall follow relevant IS codes, including IS 456 and IS 516, to ensure compliance with quality standards. The rate shall include all costs associated with labor, material, machinery,batching,transporting,placing,compacting, curing, sampling, testing, and incidental works. Shuttering costs, where required, are also deemed included in the rate of PCC. The work shall be executed with due diligence, adhering to environmental and safety measures, and ensuring compliance with the project's specifications and MoRTH standards.					
4	"1st Class Brick Masonry Work in Cement Mortar 1:3 This item includes the construction of brick masonry using 1st class burnt clay bricks, laid in cement mortar of mix ratio 1:3 (Cement: Sand), for foundations, walls, piers, columns, and other structures as per the approved drawings and technical specifications, from ground level till plinth and in superstructure above plinth level up to floor one level. The work includes thoroughly soaking the bricks in water for a minimum period of one hour prior to laying them to ensure proper bonding and to achieve maximum strength. The work shall also involve the protection of the green structure from rain during curing by suitable coverings. Curing of the masonry shall be done for a minimum period of 7 days as per standard practices to ensure the proper hydration and strength development of the mortar and masonry. The work excludes the cost of pointing, plastering, or any additional finish unless specified otherwise. The work shall be executed in accordance with the relevant CPWD and IS specifications. The final price includes the cost of procurement of 1st class bricks, cement, sand, and other necessary materials, including royalty charges, transportation to site, soaking of bricks, labor, machinery, curing, and all overheads and profit. The cost does not include pointing, plastering, or any decorative finishes unless specified separately. Safety measures and quality checks shall be implemented during all stages. Relevant Standards: CPWD Specification No. 6.4 (Brick	6.9	cum	9400	64,860.00	76,534.80

	Masonry Work) MoRTH Clause 1300 (Brick Masonry Work) "					
5	"Reinforced Cement Concrete (M25) in foundations All charges for providing and placing RCC M25 grade concrete for foundations as per approved drawings and technical specifications, conforming to MoRTH Sections 1500, 1700, and 2200. The concrete shall be produced using a batch mix plant, transported via transit mixers, and placed in position using appropriate equipment. The mix design, including approved admixtures, shall be submitted for approval by the Engineer-in Charge (EIC) before production. Aggregates shall not exceed a maximum size of 20 mm, and the concrete shall have a workable slump suitable for RCC. Concrete placement shall ensure a free-fall height of less than 1.5 m to avoid segregation and be compacted using mechanical vibrators for proper consolidation. The rate includes all formwork/shuttering costs to support concrete placement, which must ensure safety and stability. Adequate curing shall be performed for at least 7 days, following approved methods, to meet specified strength and durability. Quality control measures include sampling, testing, and certification as per IS codes like IS 456 and IS 516 to verify strength and compliance. Environmental, material handling, and safety protocols shall be adhered "	7.24	cum	7500	54,300.00	64,074.00
6	"Reinforcement Steel: All charges for providing, cutting, bending, transporting, and tying reinforcement steel of designation TMT FE 500 as per IS 1786 for construction work. The vendor shall supply all necessary steel and 18gauge black annealed binding wire. Reinforcement steel bars are to be cut, bent, and tied per approved bar bending schedules and structural drawings, ensuring precise dimensions and placements. Steel bars shall be securely tied at all intersections using 18-gauge black annealed binding wire to maintain stability during concrete placement. Laps shall conform to MoRTH specifications and as directed in drawings, with no separate payment for laps or overlaps as per MoRTH Clause 1600. Proper clear cover shall be maintained with spacers and chairs as per drawings and CPWD standards. Steel will be measured by weight in kilograms, excluding binding wire and without allowances for overlaps or wastage. The scope of work includes supply, handling,	500.98	Kg	78	39,076.44	46,110.20

	and on-site quality assurance for positioning, alignment, and compliance with specifications and as directed by EIC. Safety measures and quality checks shall be implemented during all stages, ensuring high-standard reinforcement for structural integrity. Reinforcement bars from the approved make shall only be used."					
7	Providing and Applying 1 Coat Primer and 2 Coats of Weatherproof Paint of Asian or equivalent make All charges for the preparation and application of one coat of primer followed by two coats of weatherproof paint Asian or equivalent make of the approved shade to plastered surfaces. The surface must be thoroughly cleaned to remove dirt, dust, oil, grease, efflorescence, and any other contaminants that could affect the adhesion of the paint. The primer shall be applied first, followed by two coats of weatherproof paint, ensuring even coverage across the entire surface. The paint shall be applied at a coverage rate of 1 litre per 12 square meters for each coat. The work shall be carried out in accordance with MoRTH and CPWD specifications to achieve a durable, smooth, and uniform finish that protects the surface from weathering. The final price includes the cost of all materials (primer and paint), including transportation to the site, labor for surface preparation, cleaning, and application of the primer and paint in three coats (1 coat primer + 2 coats paint). It also includes machinery, tools, curing (if applicable), and all overheads and profit. Safety measures and quality checks shall be implemented during all stages. Relevant Standards: MoRTH Clause 800 (Painting and Surface Finishing Work) IS 15489:Code of Practice for Painting of Concrete Surfaces IS 5410: Specification for Weather-Resistant Paints for Exterior Use	50.88	Sqm	100	5,088.00	6,003.84
8	Fabrication & Installation of MS Staircase	2	Nos	20000	40,000.00	47,200.00

Sub Total	247,015.94
Total CGST	22,231.44
Total SGST	22,231.44
Total	291,478.82
Round Off	0.18
Round Off Total(INR)	291,479.00

Amount in Words (INR): Two Lakh Ninety One Thousand Four Hundred Seventy Nine

APPROVER DETAILS

No	Approved By	Approved Date	Signature
1	Sandeep Khosa	20-11-2025 12:21:28	

Downloaded By Kishan Dubey (NHIP0138) 2025-11-20 13:18:23
Note*: This is Computer Generated PO and Signature is not Mandatory.

NHIT EASTERN PROJECTS PRIVATE LIMITED

NFA Cum Comparative Chart

1 PR for New Contruction of Porta Cabin foundation work received from Operation Team of Galia Toll Plaza, Kaljhar-Patachakuchi Assam Toll Road Highways Project

2 PR date and scope of works as defined in Procurement Request

3 PR & NFA cum Comparative statement is approved as per DOA.

Date- 18-11-2025

PR REF : PR/NOV25/045

Name of the Project : Galia Toll Plaza, Kaljhar-Patachakuchi Assam Toll Road Highways Project

Name of the Vendor ------>		Uom	Qty.	M/s Sky Enterprise		M/s A.K. Group		M/s Asomi Enterprise	
S.No.	Description			Rate (INR)	Amount (INR)	Rate (INR)	Amount (INR)	Rate (INR)	Amount (INR)
1	Excavation for foundation in earth, soil of all types, sand, gravel, and soft murmur, including removing the excavated material up to a distance of 50m, beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary backfiling, ramming, watering including shoring and strutting etc. all complete.	Cum	13.650	390.00	5,323.50	390.00	5,323.50	400.00	5,460.00
2	Backfilling of development area of Porta Cabin room for the depth of 2.5m with the approved borrow area material with all leads & lifts, transporting to site, spreading, grading to required slope and compaction to meet the requirement of table 300.2	Cum	54.000	500.00	27,000.00	490.00	26,460.00	490.00	26,460.00
3	All charges for supply & placing of Plain Cement Concrete (M-15 grade) in open foundations as per approved drawings and technical specifications, conforming to MoRTH Sections 1500, 1700, and 2200. The concrete shall be batched using a batch mix plant, ensuring uniformity and consistent quality. The mix shall use aggregates of size not exceeding 20 mm, with a workable slump suitable for PCC. The thickness of PCC shall be as specified in drawing. Concrete placement shall ensure a free-fall height of less than 1.5 m to prevent segregation, compacted using mechanical vibrators to achieve proper consolidation. The work includes the preparation of the foundation surface, leveling, placing concrete, and finishing exposed surfaces to achieve the required levels and smoothness. Adequate curing, as per approved methods, shall be carried out for at least 7 days to attain the desired strength. Sampling and testing shall follow relevant IS codes, including IS 456 and IS 516, to ensure compliance with quality standards. The rate shall include all costs associated with labor, material, machinery,batching,transporting,placing,compacting,curing, sampling, testing, and incidental works. Shuttering costs, where required, are also deemed included in the rate of PCC. The work shall be executed with due diligence, adhering to environmental and safety measures, and ensuring compliance with the project's specifications and MoRTH standards.	Cum	2.290	5,500.00	12,595.00	5,200.00	11,908.00	5,250.00	12,022.50

4	1st Class Brick Masonry Work in Cement Mortar 1:3 This item includes the construction of brick masonry using 1st class burnt clay bricks, laid in cement mortar of mix ratio 1:3 (Cement: Sand), for foundations, walls, piers, columns, and other structures as per the approved drawings and technical specifications, from ground level till plinth and in superstructure above plinth level up to floor one level. The work includes thoroughly soaking the bricks in water for a minimum period of one hour prior to laying them to ensure proper bonding and to achieve maximum strength. The work shall also involve the protection of the green structure from rain during curing by suitable coverings. Curing of the masonry shall be done for a minimum period of 7 days as per standard practices to ensure the proper hydration and strength development of the mortar and masonry. The work excludes the cost of pointing, plastering, or any additional finish unless specified otherwise. The work shall be executed in accordance with the relevant CPWD and IS specifications. The final price includes the cost of procurement of 1st class bricks, cement, sand, and other necessary materials, including royalty charges, transportation to site, soaking of bricks, labor, machinery, curing, and all overheads and profit. The cost does not include pointing, plastering, or any decorative finishes unless specified separately. Safety measures and quality checks shall be implemented during all stages. Relevant Standards: CPWD Specification No. 6.4 (Brick Masonry Work) MoRTH Clause 1300 (Brick Masonry Work)	Cum	6.900	9,400.00	64,860.00	9,400.00	64,860.00	9,500.00	65,550.00
5	Reinforced Cement Concrete (M25) in foundations All charges for providing and placing RCC M25 grade concrete for foundations as per approved drawings and technical specifications, conforming to MoRTH Sections 1500, 1700, and 2200. The concrete shall be produced using a batch mix plant, transported via transit mixers, and placed in position using appropriate equipment. The mix design, including approved admixtures, shall be submitted for approval by the Engineer-in Charge (EIC) before production. Aggregates shall not exceed a maximum size of 20 mm, and the concrete shall have a workable slump suitable for RCC. Concrete placement shall ensure a free-fall height of less than 1.5 m to avoid segregation and be compacted using mechanical vibrators for proper consolidation. The rate includes all formwork/shuttering costs to support concrete placement, which must ensure safety and stability. Adequate curing shall be performed for at least 7 days, following approved methods, to meet specified strength and durability. Quality control measures include sampling, testing, and certification as per IS codes like IS 456 and IS 516 to verify strength and compliance. Environmental, material handling, and safety protocols shall be adhered	Cum	7.240	7,500.00	54,300.00	7,500.00	54,300.00	7,500.00	54,300.00

6	Reinforcement Steel: All charges for providing, cutting, bending, transporting, and tying reinforcement steel of designation TMT FE 500 as per IS 1786 for construction work. The vendor shall supply all necessary steel and 18gauge black annealed binding wire. Reinforcement steel bars are to be cut, bent, and tied per approved bar bending schedules and structural drawings, ensuring precise dimensions and placements. Steel bars shall be securely tied at all intersections using 18-gauge black annealed binding wire to maintain stability during concrete placement. Laps shall conform to MoRTH specifications and as directed in drawings, with no separate payment for laps or overlaps as per MoRTH Clause 1600. Proper clear cover shall be maintained with spacers and chairs as per drawings and CPWD standards. Steel will be measured by weight in kilograms, excluding binding wire and without allowances for overlaps or wastage. The scope of work includes supply, handling, and on-site quality assurance for positioning, alignment, and compliance with specifications and as directed by EIC. Safety measures and quality checks shall be implemented during all stages, ensuring high-standard reinforcement for structural integrity. Reinforcement bars from the approved make shall only be used.	Kg	500.980	85.00	42,583.30	78.00	39,076.44	80.00	40,078.40
7	charges for the preparation and application of one coat of primer followed by two coats of weatherproof paint Asian or equivalent make of the approved shade to plastered surfaces. The surface	Sqm	50.880	110.00	5,596.80	100.00	5,088.00	100.00	5,088.00
8	Fabrication & Installation of MS Staircase	Nos	2	25,000.00	50,000.00	20,000.00	40,000.00	22,000.00	44,000.00
	Total Basic Cost				**2,62,258.60**		**2,47,015.94**		**2,52,958.90**
	Commercial Terms								
❖	Other cost/Remarks/Responsive			N.A.		N.A.		N.A.	
❖	GST			GST 18%	**47,206.55**	GST 18%	**44,462.87**	GST 18%	**45,532.60**
❖	Delivery Time			Within 30-45 Working days		Within 30 Working days		Within 45 working days	
❖	Warranty/Maintenance			3 Months		3 Months		3 Months	
❖	Freight Charges			inclusive		inclusive		inclusive	
❖	Payment Terms			Payment shall be made after Completion of work and submission of invoice within 45 days		Payment shall be made after Completion of work and submission of invoice within 45 days		Payment shall be made after Completion of work and submission of invoice within 45 days	
❖	**Total Cost**				**3,09,465.00**		**2,91,479.00**		**2,98,492.00**
❖	**Ranking**			**L3**		**L1**		**L2**	
❖	*** It is Proposed to Place order to M/s A.K. Group being L-1 vendor.**								

	Purchase Committee	
	Prepared By -	
	Manager – Procurement Team	
	Sr. Manager / Manager – F&A Team	
	HOD User Team / SPV Head	
	HOD – Procurement Team	

Requirements - Container Foundation PR001-Nov25

Reply | Reply All | Forward

Mon 17-11-2025 11:09

TP Team Procurement

To

Cc Kishan Dubey; Vinay Jindal; Sandeep Khosa; Rishpa Manger

Bcc C Mahesh; Amitav Chakraborty; ASOMI ENTERPRISE; Sky Enterprise; Pranab Dutta; AK Group

This message was sent with High importance.

BoQ - PR 001 Nov..xlsx
111 KB

Dear All,

NHIT Eastern Projects Private Limited is going to **enquire for Civil Works for Construction of Container Foundation at Galia Toll Plaza.**

NEPPL being "Employer" intends to invite quotation from eligible Bidders for providing aforesaid services in the format attached as BOQ.

In addition to the above, you are requested to take note of the following:

1. The employer reserves the right to reject any or all the Bids/Quotations or cancel/ withdraw the Tender/RFQ without assigning any reason whatsoever and in such case, no Bidder/ intending Bidders/Vendors shall have any claim arising out of such action.
2. Prices shall be inclusive of all Taxes & Duties except GST. GST shall be paid extra at actual.

In view of the above, you are requested to submit your most competitive offer for mentioned above work along with the duly filled attached Company Particulars sheet latest by or before **18.11.2025.**

Thanks & Regards,
Team Procurement
VJ

Purchase Requisition

Requested By: C Mahesh (NEPP117)
Department: Operations - Capex(DEPT003)
Custom Ship Location Name: KPRP-Cap - Ops(000006003)

PR No: PR/NOV25/045
PR Date: 10-11-2025
Final Status: Approved

Order Type: Normal

Sl.No	Product Name	Product Description	Unit Type	Product Type	Category	Sub Category	Project	Cost Code	Price	Quantity	Total Price	Required By	Remarks
1	Excavation Backfilling for all types and sizes of foundations,trenches and drains or for any other p	Excavation for foundation in earth, soil of all types, sand, gravel, and soft murmur, including removing the excavated material up to a distance of 50m, beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary backfiling, ramming, watering including shoring and strutting etc. all complete.	cum	both	Material Capex		Kaljhar - Patachar kuchi(PRJ004)	Kaljhar - Patachar kuchi - Capex(TSK001)	382	13.65	5,214.30	11-11-2025	
2	Soil & Sand Backfilling	Backfilling of development area of Porta Cabin room for the depth of 2.5m with the approved borrow area material with all leads & lifts, transporting to site, spreading, grading to required slope and compaction to meet the requirement of table 300.2	cum	both	Material Capex		Kaljhar - Patachar kuchi(PRJ004)	Kaljhar - Patachar kuchi - Capex(TSK001)	435	54	23,490.00	11-11-2025	
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete m	All charges for supply & placing of Plain Cement Concrete (M-15 grade) in open foundations as per approved drawings and technical specifications, conforming to MoRTH Sections 1500, 1700, and 2200. The concrete shall be batched using a batch mix plant, ensuring uniformity and	cum	both	Material Capex		Kaljhar - Patachar kuchi(PRJ004)	Kaljhar - Patachar kuchi - Capex(TSK001)	4990	2.29	11,427.10	11-11-2025	

Note*: This is Computer Generated Document and Signature is not Mandatory.

consistent quality. The mix shall use aggregates of size not exceeding 20 mm, with a workable slump suitable for PCC. The thickness of PCC shall be as specified in drawing. Concrete placement shall ensure a free-fall height of less than 1.5 m to prevent segregation, compacted using mechanical vibrators to achieve proper consolidation. The work includes the preparation of the foundation surface, leveling, placing concrete, and finishing exposed surfaces to achieve the required levels and smoothness. Adequate curing, as per approved methods, shall be carried out for at least 7 days to attain the desired strength. Sampling and testing shall follow relevant IS codes, including IS 456 and IS 516, to ensure compliance with quality standards. The rate shall include all costs associated with labor, material, mac hinery,batching,tran sporting,placing,co mpacting, curing, sampling, testing, and incidental works. Shuttering costs, where required, are also deemed included in the rate of PCC. The work shall be executed with due diligence, adhering to environmental and safety measures, and ensuring compliance with the project's specifications and MoRTH standards.

		with modular well burnt clay bricks of crushing strength not less than 25 kg/sqcm a	brick masonry using 1st class burnt clay bricks, laid in cement mortar of mix ratio 1:3 (Cement: Sand), for foundations, walls, piers, columns, and other structures as per the approved drawings and technical specifications, from ground level till plinth and in superstructure above plinth level up to floor one level. The work includes thoroughly soaking the bricks in water for a minimum period of one hour prior to laying them to ensure proper bonding and to achieve maximum strength. The work shall also involve the protection of the green structure from rain during curing by suitable coverings. Curing of the masonry shall be done for a minimum period of 7 days as per standard practices to ensure the proper hydration and strength development of the mortar and masonry. The work excludes the cost of pointing, plastering, or any additional finish unless specified otherwise. The work shall be executed in accordance with the relevant CPWD and IS specifications. The final price includes the cost of procurement of 1st class bricks, cement, sand, and other necessary materials, including royalty charges, transportation to site, soaking of bricks, labor, machinery, curing, and all overheads and profit. The cost does not include pointing, plastering, or any decorative finishes unless specified separately.		

Note*: This is Computer Generated Document and Signature is not Mandatory.

		Safety measures and quality checks shall be implemented during all stages. Relevant Standards: CPWD Specification No. 6.4 (Brick Masonry Work) MoRTH Clause 1300 (Brick Masonry Work) "									
5	Providing and laying nominal mix reinforced (M-25) cement concrete with crushed stone aggregate usin	"Reinforced Cement Concrete (M25) in foundations All charges for providing and placing RCC M25 grade concrete for foundations as per approved drawings and technical specifications, conforming to MoRTH Sections 1500, 1700, and 2200. The concrete shall be produced using a batch mix plant, transported via transit mixers, and placed in position using appropriate equipment. The mix design, including approved admixtures, shall be submitted for approval by the Engineer-in Charge (EIC) before production. Aggregates shall not exceed a maximum size of 20 mm, and the concrete shall have a workable slump suitable for RCC. Concrete placement shall ensure a free-fall height of less than 1.5 m to avoid segregation and be compacted using mechanical vibrators for proper consolidation. The rate includes all formwork/shuttering costs to support concrete placement, which must ensure safety and stability. Adequate curing shall be performed for at least 7 days	cum	both	Material Capex	Kaljhar - Patachar kuchi(PRJ004)	Kaljhar - Patachar kuchi - Capex(TSK001)	7150	7.24	51,766.00	11-11-2025

		and durability. Quality control measures include sampling, testing, and certification as per IS codes like IS 456 and IS 516 to verify strength and compliance. Environmental, material handling, and safety protocols shall be adhered "									
6	Providing & Binding of TMT Bar for Tie Beam, Column & Slab with scope including materials, manpowers	"Reinforcement Steel: All charges for providing, cutting, bending, transporting, and tying reinforcement steel of designation TMT FE 500 as per IS 1786 for construction work. The vendor shall supply all necessary steel and 18gauge black annealed binding wire. Reinforcement steel bars are to be cut, bent, and tied per approved bar bending schedules and structural drawings, ensuring precise dimensions and placements. Steel bars shall be securely tied at all intersections using 18-gauge black annealed binding wire to maintain stability during concrete placement. Laps shall conform to MoRTH specifications and as directed in drawings, with no separate payment for laps or overlaps as per MoRTH Clause 1600. Proper clear cover shall be maintained with spacers and chairs as per drawings and CPWD standards. Steel will be measured by weight in kilograms, excluding binding wire and without allowances for overlaps or wastage. The scope of work includes supply, handling, and on-site quality	Kg	both	Material Capex	Kaljhar - Patachar kuchi(PRJ004)	Kaljhar - Patachar kuchi - Capex(TSK001)	80	500.98	40,078.40	11-11-2025

		assurance for positioning, alignment, and compliance with specifications and as directed by EIC. Safety measures and quality checks shall be implemented during all stages, ensuring high-standard reinforcement for structural integrity. Reinforcement bars from the approved make shall only be used."									
7	Wall painting (two coats) with acrylic emulsion paint of approved brand and manufacture on new sur	Providing and Applying 1 Coat Primer and 2 Coats of Weatherproof Paint of Asian or equivalent make All charges for the preparation and application of one coat of primer followed by two coats of weatherproof paint Asian or equivalent make of the approved shade to plastered surfaces. The surface must be thoroughly cleaned to remove dirt, dust, oil, grease, efflorescence, and any other contaminants that could affect the adhesion of the paint. The primer shall be applied first, followed by two coats of weatherproof paint, ensuring even coverage across the entire surface. The paint shall be applied at a coverage rate of 1 litre per 12 square meters for each coat. The work shall be carried out in accordance with MoRTH and CPWD specifications to achieve a durable, smooth, and uniform finish that protects the surface from weathering	Sqm	both	Material Capex	Kaljhar - Patachar kuchi(PRJ004)	Kaljhar - Patachar kuchi - Capex(TSK001)	83	50.88	4,223.04	11-11-2025

		and paint), including transportation to the site, labor for surface preparation, cleaning, and application of the primer and paint in three coats (1 coat primer + 2 coats paint). It also includes machinery, tools, curing (if applicable), and all overheads and profit. Safety measures and quality checks shall be implemented during all stages. Relevant Standards: MoRTH Clause 800 (Painting and Surface Finishing Work) IS 15489:Code of Practice for Painting of Concrete Surfaces IS 5410: Specification for Weather-Resistant Paints for Exterior Use										
8	MS Staircase	Fabrication & Installation of MS Staircase	Nos	both	Material Capex	Kaljhar - Patachar kuchi(PRJ004)	Kaljhar - Patachar kuchi - Capex(TSK001)	9800	2	19,600.00	11-11-2025	

Remarks:

Approval 1

Amitav Chakraborty (NEPP018)

Approval Status: Approved

Requested Date and Time: 10-11-2025 01:47:07

Approval Date and Time: 10-11-2025 01:54:19

Approval 2

Priyabrata Ghosh (NHIP101)

Approval Status: Approved

Requested Date and Time: 10-11-2025 01:47:07

Approval Date and Time: 10-11-2025 04:41:03

Approval 3

Naveen Kumar (NHIP049)

Approval Status: Approved

Requested Date and Time: 10-11-2025 01:47:07

Approval Date and Time: 10-11-2025 04:43:35

Approval 4

Pawan Kumar (EMP004)

Approval Status: Approved

Requested Date and Time: 10-11-2025 01:47:07

Approval Date and Time: 10-11-2025 06:04:12

Note*: This is Computer Generated Document and Signature is not Mandatory.

Team Procurement

From: Sky Enterprise <skyenterprise129@gmail.com>
Sent: 17 November 2025 18:01
To: Team Procurement
Cc: Kishan Dubey; Vinay Jindal; Sandeep Khosa; Rishpa Manger
Subject: Re: Requirements - Container Foundation PR001-Nov25
Attachments: BoQ - PR 001 Nov. (3).xlsx; Sky enterprise documents.pdf; Sky enterprise documents.pdf

Caution: This is an external email and may be malicious. Please take care when clicking links or opening attachments.

Dear Sir/Ma'am,

Sky Enterprise is hereby participating in the tender for Civil Works for Construction of Container Foundation at Galia Toll Plaza. Please find the attached quotation and documents.

Thank you.

On Mon, Nov 17, 2025 at 11:08 AM Team Procurement <procurement@nhit.co.in> wrote:

> Dear All,
>
> **NHIT Eastern Projects Private Limited** is going to **enquire for Civil Works for Construction of Container Foundation at Galia Toll Plaza.**
>
> NEPPL being "Employer" intends to invite quotation from eligible Bidders for providing aforesaid services in the format attached as BOQ.

NHIT
National Highways Infra Trust

Name of Project:- Kachugaon-Rakhaldubi Bus Junction-Kaljhar- Patacharkuchi at NH-27 Assam Road Projects

BILL OF QUANTITIES(BOQ) - of The New Porta Cabin For Galia Toll Plaza at ASSAM PROJECTS

Item No.	Description	Unit	Total Quantity	Tentative Rate	Tentative Amount	Remark
1	Excavation for foundation in earth, soil of all types, sand, gravel, and soft murmur, including removing the excavated material up to a distance of 50m, beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary backfilling, ramming, watering including shoring and strutting etc. all complete.	Cu.m	13.650	390.00	5323.50	
2	Backfilling of development area of Porta Cabin room for the depth of 2.5m with the approved borrow area material with all leads & lifts, transporting to site, spreading, grading to required slope and compaction to meet the requirement of table 300.2	Cu.m	54.000	500.00	27000.00	
3	All charges for supply & placing of Plain Cement Concrete (M-15 grade) in open foundations as per approved drawings and technical specifications, conforming to MoRTH Sections 1500, 1700, and 2200. The concrete shall be batched using a batch mix plant, ensuring uniformity and consistent quality. The mix shall use aggregates of size not exceeding 20 mm, with a workable slump suitable for PCC. The thickness of PCC shall be as specified in drawing. Concrete placement shall ensure a free-fall height of less than 1.5 m to prevent segregation, compacted using mechanical vibrators to achieve proper consolidation. The work includes the preparation of the foundation surface, leveling, placing concrete, and finishing exposed surfaces to achieve the required levels and smoothness. Adequate curing, as per approved methods, shall be carried out for at least 7 days to attain the desired strength. Sampling and testing shall follow relevant IS codes, including IS 456 and IS 516, to ensure compliance with quality standards. The rate shall include all costs associated with labor, material, machinery,batching,transporting,placing,compacting, curing, sampling, testing, and incidental works. Shuttering costs, where required, are also deemed included in the rate of PCC. The work shall be executed with due diligence, adhering to environmental and safety measures, and ensuring compliance with the project's specifications and MoRTH standards.	Cu.m	2.290	5500.00	12595.00	
4	1st Class Brick Masonry Work in Cement Mortar 1:3 This item includes the construction of brick masonry using 1st class burnt clay bricks, laid in cement mortar of mix ratio 1:3 (Cement: Sand), for foundations, walls, piers, columns, and other structures as per the approved drawings and technical specifications, from ground level till plinth and in superstructure above plinth level up to floor one level. The work includes thoroughly soaking the bricks in water for a minimum period of one hour prior to laying them to ensure proper bonding and to achieve maximum strength. The work shall also involve the protection of the green structure from rain during curing by suitable coverings. Curing of the masonry shall be done for a minimum period of 7 days as per standard practices to ensure the proper hydration and strength development of the mortar and masonry. The work excludes the cost of pointing, plastering, or any additional finish unless specified otherwise. The work shall be executed in accordance with the relevant CPWD and IS specifications. The final price includes the cost of procurement of 1st class bricks, cement, sand, and other necessary materials, including royalty charges, transportation to site, soaking of bricks, labor, machinery, curing, and all overheads and profit. The cost does not include pointing, plastering, or any decorative finishes unless specified separately. Safety measures and quality checks shall be implemented during all stages. Relevant Standards: CPWD Specification No. 6.4 (Brick Masonry Work) MoRTH Clause 1300 (Brick Masonry Work)	Cu.m	6.900	9400.00	64860.00	
5	Reinforced Cement Concrete (M25) in foundations All charges for providing and placing RCC M25 grade concrete for foundations as per approved drawings and technical specifications, conforming to MoRTH Sections 1500, 1700, and 2200. The concrete shall be produced using a batch mix plant, transported via transit mixers, and placed in position using appropriate equipment. The mix design, including approved admixtures, shall be submitted for approval by the Engineer-in Charge (EIC) before production. Aggregates shall not exceed a maximum size of 20 mm, and the concrete shall have a workable slump suitable for RCC. Concrete placement shall ensure a free-fall height of less than 1.5 m to avoid segregation and be compacted using mechanical vibrators for proper consolidation. The rate includes all formwork/shuttering costs to support concrete placement, which must ensure safety and stability. Adequate curing shall be performed for at least 7 days, following approved methods, to meet specified strength and durability. Quality control measures include sampling, testing, and certification as per IS codes like IS 456 and IS 516 to verify strength and compliance. Environmental, material handling, and safety protocols shall be adhered	Cu.m	7.236	7500.00	54270.00	For Galia Toll Plaza, Foundation of Porta cabin (Conference cum Manager Room)

6	Reinforcement Steel: All charges for providing, cutting, bending, transporting, and tying reinforcement steel of designation TMT FE 500 as per IS 1786 for construction work. The vendor shall supply all necessary steel and 18gauge black annealed binding wire. Reinforcement steel bars are to be cut, bent, and tied per approved bar bending schedules and structural drawings, ensuring precise dimensions and placements. Steel bars shall be securely tied at all intersections using 18-gauge black annealed binding wire to maintain stability during concrete placement. Laps shall conform to MoRTH specifications and as directed in drawings, with no separate payment for laps or overlaps as per MoRTH Clause 1600. Proper clear cover shall be maintained with spacers and chairs as per drawings and CPWD standards. Steel will be measured by weight in kilograms, excluding binding wire and without allowances for overlaps or wastage. The scope of work includes supply, handling, and on-site quality assurance for positioning, alignment, and compliance with specifications and as directed by EIC. Safety measures and quality checks shall be implemented during all stages, ensuring high-standard reinforcement for structural integrity. Reinforcement bars from the approved make shall only be used.	Kgs.	500.978	85.00	42583.11
7	Providing and Applying 1 Coat Primer and 2 Coats of Weatherproof Paint of Asian or equivalent make All charges for the preparation and application of one coat of primer followed by two coats of weatherproof paint Asian or equivalent make of the approved shade to plastered surfaces. The surface must be thoroughly cleaned to remove dirt, dust, oil, grease, efflorescence, and any other contaminants that could affect the adhesion of the paint. The primer shall be applied first, followed by two coats of weatherproof paint, ensuring even coverage across the entire surface. The paint shall be applied at a coverage rate of 1 litre per 12 square meters for each coat. The work shall be carried out in accordance with MoRTH and CPWD specifications to achieve a durable, smooth, and uniform finish that protects the surface from weathering. The final price includes the cost of all materials (primer and paint), including transportation to the site, labor for surface preparation, cleaning, and application of the primer and paint in three coats (1 coat primer + 2 coats paint). It also includes machinery, tools, curing (if applicable), and all overheads and profit. Safety measures and quality checks shall be implemented during all stages. Relevant Standards: MoRTH Clause 800 (Painting and Surface Finishing Work) IS 15489:Code of Practice for Painting of Concrete Surfaces IS 5410: Specification for Weather-Resistant Paints for Exterior Use	Sq.m.	50.880	110.00	5596.80
8	Fabrication & Installation of MS Staircase	Nos.	2	25000.00	50000.00
				Total Amount	**2,62,228.411**
				GST 18%	**47,201.114**
				Grand Total	**3,09,429.525**

Team Procurement

From: AK Group <groupak491@gmail.com>
Sent: 17 November 2025 18:10
To: Team Procurement
Cc: Kishan Dubey; Vinay Jindal; Sandeep Khosa; Rishpa Manger
Subject: Re: Requirements - Container Foundation PR001-Nov25
Attachments: Documents of AK Group.pdf; BoQ - PR 001 Nov..xlsx; AK group quotation.pdf

Caution: This is an external email and may be malicious. Please take care when clicking links or opening attachments.

Sir/Madam,

AK Group is hereby participating in the tender for- Construction of Container Foundation at Galia Toll Plaza. The BOQ has been filled up and attached herewith with other documents. Please find the attachment.

Warm Regards,

A K Group
Contact: 9706346509, 8134040915

A.K. GROUP

QUOTATION FOR 'Construction of Container Foundation at Galia Toll Plaza'

To,
The Procurement Team,
NHIT Eastern Projects Private Limited,
Dwarka, New Delhi – 110077

Dear Sir/Ma'am,
With reference to the enquiry for the work- 'Construction of Container Foundation at Galia Toll Plaza', we are pleased to submit our most competitive quotation.

Name of Project:- Kachugaon-Rakhaldubi Bus Junction-Kaljhar-Patacharkuchi at NH-27 Assam Road Projects

BILL OF QUANTITIES(BOQ) - of The New Porta Cabin For Galia Toll Plaza at ASSAM PROJECTS

Item No.	Description	Unit	Total Quantity	Tentative Rate	Tentative Amount	Remark
1	Excavation for foundation in earth, soil of all types, sand, gravel, and soft murmur, including removing the excavated material up to a distance of 50m, beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary backfiling, ramming, watering including shoring and strutting etc. all complete.	Cu.m	13.650	390.00	5323.50	For Galia Toll Plaza, Foundation of Porta cabin (Conference cum Manager Room)
2	Backfilling of development area of Porta Cabin room for the depth of 2.5m with the approved borrow area material with all leads & lifts, transporting to site, spreading, grading to required slope and compaction to meet the requirement of table 300.2	Cu.m	54.000	490.00	26460.00	

3	All charges for supply & placing of Plain Cement Concrete (M-15 grade) in open foundations as per approved drawings and technical specifications, conforming to MoRTH Sections 1500, 1700, and 2200. The concrete shall be batched using a batch mix plant, ensuring uniformity and consistent quality. The mix shall use aggregates of size not exceeding 20 mm, with a workable slump suitable for PCC. The thickness of PCC shall be as specified in drawing. Concrete placement shall ensure a free-fall height of less than 1.5 m to prevent segregation, compacted using mechanical vibrators to achieve proper consolidation. The work includes the preparation of the foundation surface, leveling, placing concrete, and finishing exposed surfaces to achieve the required levels and smoothness. Adequate curing, as per approved methods, shall be carried out for at least 7 days to attain the desired strength. Sampling and testing shall follow relevant IS codes, including IS 456 and IS 516, to ensure compliance with quality standards. The rate shall include all costs associated with labor, material, machinery,batching,transporting,placing,compacting, curing, sampling, testing, and incidental works. Shuttering costs, where required, are also deemed included in the rate of PCC. The work shall be executed with due diligence, adhering to environmental and safety measures, and ensuring compliance with the project's specifications and MoRTH standards.	Cu.m	2.290	5200.00	11908.00	
4	1st Class Brick Masonry Work in Cement Mortar 1:3 This item includes the construction of brick masonry using 1st class burnt clay bricks, laid in cement mortar of mix ratio 1:3 (Cement: Sand), for foundations, walls, piers, columns, and other structures as per the approved drawings and technical specifications, from ground level till plinth and in superstructure above plinth level up to floor one level. The work includes thoroughly soaking the bricks in water for a minimum period of one hour prior to laying them to ensure proper bonding and to achieve maximum strength. The work shall also involve the protection of the green structure from rain during curing by suitable coverings. Curing of the masonry shall be done for a minimum period of 7 days as per standard practices to ensure the proper hydration and strength development of the mortar and masonry. The work excludes the cost of pointing, plastering, or any additional finish unless specified otherwise. The work shall be executed in accordance with the relevant CPWD and IS specifications. The final price includes the cost of procurement of 1st class bricks, cement, sand, and other necessary materials, including royalty charges, transportation to site, soaking of bricks, labor, machinery, curing, and all overheads and profit. The cost does not include pointing, plastering, or any decorative finishes unless specified separately. Safety measures and quality checks shall be implemented during all stages. Relevant Standards: CPWD Specification No. 6.4 (Brick Masonry Work) MoRTH Clause 1300 (Brick Masonry Work)	Cu.m	6.900	9400.00	64860.00	

5	Reinforced Cement Concrete (M25) in foundations All charges for providing and placing RCC M25 grade concrete for foundations as per approved drawings and technical specifications, conforming to MoRTH Sections 1500, 1700, and 2200. The concrete shall be produced using a batch mix plant, transported via transit mixers, and placed in position using appropriate equipment. The mix design, including approved admixtures, shall be submitted for approval by the Engineer-in Charge (EIC) before production. Aggregates shall not exceed a maximum size of 20 mm, and the concrete shall have a workable slump suitable for RCC. Concrete placement shall ensure a free-fall height of less than 1.5 m to avoid segregation and be compacted using mechanical vibrators for proper consolidation. The rate includes all formwork/shuttering costs to support concrete placement, which must ensure safety and stability. Adequate curing shall be performed for at least 7 days, following approved methods, to meet specified strength and durability. Quality control measures include sampling, testing, and certification as per IS codes like IS 456 and IS 516 to verify strength and compliance. Environmental, material handling, and safety protocols shall be adhered	Cu.m	7.236 7.240	7500.00	54270.00 54300	
6	Reinforcement Steel: All charges for providing, cutting, bending, transporting, and tying reinforcement steel of designation TMT FE 500 as per IS 1786 for construction work. The vendor shall supply all necessary steel and 18gauge black annealed binding wire. Reinforcement steel bars are to be cut, bent, and tied per approved bar bending schedules and structural drawings, ensuring precise dimensions and placements. Steel bars shall be securely tied at all intersections using 18-gauge black annealed binding wire to maintain stability during concrete placement. Laps shall conform to MoRTH specifications and as directed in drawings, with no separate payment for laps or overlaps as per MoRTH Clause 1600. Proper clear cover shall be maintained with spacers and chairs as per drawings and CPWD standards. Steel will be measured by weight in kilograms, excluding binding wire and without allowances for overlaps or wastage. The scope of work includes supply, handling, and on-site quality assurance for positioning, alignment, and compliance with specifications and as directed by EIC. Safety measures and quality checks shall be implemented during all stages, ensuring high-standard reinforcement for structural integrity. Reinforcement bars from the approved make shall only be used.	Kgs.	500.978 500.980	78.00	39076.27 39076.44	

7	Providing and Applying 1 Coat Primer and 2 Coats of Weatherproof Paint of Asian or equivalent make All charges for the preparation and application of one coat of primer followed by two coats of weatherproof paint Asian or equivalent make of the approved shade to plastered surfaces. The surface must be thoroughly cleaned to remove dirt, dust, oil, grease, efflorescence, and any other contaminants that could affect the adhesion of the paint. The primer shall be applied first, followed by two coats of weatherproof paint, ensuring even coverage across the entire surface. The paint shall be applied at a coverage rate of 1 litre per 12 square meters for each coat. The work shall be carried out in accordance with MoRTH and CPWD specifications to achieve a durable, smooth, and uniform finish that protects the surface from weathering. The final price includes the cost of all materials (primer and paint), including transportation to the site, labor for surface preparation, cleaning, and application of the primer and paint in three coats (1 coat primer + 2 coats paint). It also includes machinery, tools, curing (if applicable), and all overheads and profit. Safety measures and quality checks shall be implemented during all stages. Relevant Standards: MoRTH Clause 800 (Painting and Surface Finishing Work) IS 15489:Code of Practice for Painting of Concrete Surfaces IS 5410: Specification for Weather-Resistant Paints for Exterior Use	Sq.m.	50.880	100.00	5088.00	
8	Fabrication & Installation of MS Staircase	Nos.	2	20000.00	40000.00	-247015.94
				Total Amount	**246,985.767**	
				GST 18%	**44,457.438**	
				Grand Total	**291,443.205**	

Total In Words (with GST): Rupees Two Lakhs Ninety One Thousand Four Hundred Forty Three and Twenty Paise Only

We assure you of our best services and timely execution of the assignment as per the requirement.

Thanking You.

Yours sincerely,

Akash Hazarika
A.K. GROUP

Akash Hazarika, Proprietor
Proprietor, AK Group

Team Procurement

From: ASOMI ENTERPRISE <enterpriseasomi9@gmail.com>
Sent: 17 November 2025 18:17
To: Team Procurement
Cc: Kishan Dubey; Vinay Jindal; Sandeep Khosa; Rishpa Manger
Subject: Re: Requirements - Container Foundation PR001-Nov25
Attachments: BoQ - PR 001 Nov..xlsx; Asomi quotation.pdf; Asomi documents.pdf

Caution: This is an external email and may be malicious. Please take care when clicking links or opening attachments.

Respected Sir/Madam,

With reference to the above enquiry, we are pleased to submit our quotation and documents for **Construction of Container Foundation at Galia Toll Plaza.**

Thanking you.

On Mon, Nov 17, 2025 at 11:08 AM Team Procurement <procurement@nhit.co.in> wrote:

Dear All,

NHIT Eastern Projects Private Limited is going to **enquire for Civil Works for Construction of Container Foundation at Galia Toll Plaza.**

NEPPL being "Employer" intends to invite quotation from eligible Bidders for providing aforesaid services in the format attached as BOQ.

Asomi Enterprise

Second Floor, H.No.3, Maya Path, Six Mile, Guwahati, 781022, Ph: 9706346509

Ref No.: *Date:*

To,
Team Procurement,
NHIT Eastern Projects Private Limited,
Dwarka, New Delhi – 110077

Subject: Submission of Quotation for Construction of Container Foundation at Galia Toll Plaza.

Respected Sir/Madam,

With reference to the above enquiry, we are pleased to submit our quotation for **Construction of Container Foundation at Galia Toll Plaza.**
The details are as follows:

Name of Project:- Kachugaon-Rakhaldubi Bus Junction-Kaljhar-Patacharkuchi at NH-27 Assam Road Projects

BILL OF QUANTITIES(BOQ) - of The New Porta Cabin For Galia Toll Plaza at ASSAM PROJECTS

Item No.	Description	Unit	Total Quantity	Tentative Rate	Tentative Amount	Remark
1	Excavation for foundation in earth, soil of all types, sand, gravel, and soft murmur, including removing the excavated material up to a distance of 50m, beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary backfiling, ramming, watering including shoring and strutting etc. all complete.	Cu.m	13.650	400.00	5460.00	For Galia Toll Plaza, Foundation of Porta cabin (Conference cum Manager Room)
2	Backfilling of development area of Porta Cabin room for the depth of 2.5m with the approved borrow area material with all leads & lifts, transporting to site, spreading, grading to required slope and compaction to meet the requirement of table 300.2	Cu.m	54.000	490.00	26460.00	

3	All charges for supply & placing of Plain Cement Concrete (M-15 grade) in open foundations as per approved drawings and technical specifications, conforming to MoRTH Sections 1500, 1700, and 2200. The concrete shall be batched using a batch mix plant, ensuring uniformity and consistent quality. The mix shall use aggregates of size not exceeding 20 mm, with a workable slump suitable for PCC. The thickness of PCC shall be as specified in drawing. Concrete placement shall ensure a free-fall height of less than 1.5 m to prevent segregation, compacted using mechanical vibrators to achieve proper consolidation. The work includes the preparation of the foundation surface, leveling, placing concrete, and finishing exposed surfaces to achieve the required levels and smoothness. Adequate curing, as per approved methods, shall be carried out for at least 7 days to attain the desired strength. Sampling and testing shall follow relevant IS codes, including IS 456 and IS 516, to ensure compliance with quality standards. The rate shall include all costs associated with labor, material, machinery,batching,transporting,placing,compactin g, curing, sampling, testing, and incidental works. Shuttering costs, where required, are also deemed included in the rate of PCC. The work shall be executed with due diligence, adhering to environmental and safety measures, and ensuring compliance with the project's specifications and MoRTH standards.	Cu.m	2.290	5250.00	12022.50	
4	1st Class Brick Masonry Work in Cement Mortar 1:3 This item includes the construction of brick masonry using 1st class burnt clay bricks, laid in cement mortar of mix ratio 1:3 (Cement: Sand), for foundations, walls, piers, columns, and other structures as per the approved drawings and technical specifications, from ground level till plinth and in superstructure above plinth level up to floor one level. The work includes thoroughly soaking the bricks in water for a minimum period of one hour prior to laying them to ensure proper bonding and to achieve maximum strength. The work shall also involve the protection of the green structure from rain during curing by suitable coverings. Curing of the masonry shall be done for a minimum period of 7 days as per standard practices to ensure the proper hydration and strength development of the mortar and masonry. The work excludes the cost of pointing, plastering, or any additional finish unless specified otherwise. The work shall be executed in accordance with the relevant CPWD and IS specifications. The final price includes the cost of procurement of 1st class bricks, cement, sand, and other necessary materials, including royalty charges, transportation to site, soaking of bricks, labor, machinery, curing, and all overheads and profit. The cost does not include pointing, plastering, or	Cu.m	6.900	9500.00	65550.00	

	any decorative finishes unless specified separately. Safety measures and quality checks shall be implemented during all stages. Relevant Standards: CPWD Specification No. 6.4 (Brick Masonry Work) MoRTH Clause 1300 (Brick Masonry Work)					
5	Reinforced Cement Concrete (M25) in foundations All charges for providing and placing RCC M25 grade concrete for foundations as per approved drawings and technical specifications, conforming to MoRTH Sections 1500, 1700, and 2200. The concrete shall be produced using a batch mix plant, transported via transit mixers, and placed in position using appropriate equipment. The mix design, including approved admixtures, shall be submitted for approval by the Engineer-in Charge (EIC) before production. Aggregates shall not exceed a maximum size of 20 mm, and the concrete shall have a workable slump suitable for RCC. Concrete placement shall ensure a free-fall height of less than 1.5 m to avoid segregation and be compacted using mechanical vibrators for proper consolidation. The rate includes all formwork/shuttering costs to support concrete placement, which must ensure safety and stability. Adequate curing shall be performed for at least 7 days, following approved methods, to meet specified strength and durability. Quality control measures include sampling, testing, and certification as per IS codes like IS 456 and IS 516 to verify strength and compliance. Environmental, material handling, and safety protocols shall be adhered	Cu.m	7.236	7500.00	54270.00	
6	Reinforcement Steel: All charges for providing, cutting, bending, transporting, and tying reinforcement steel of designation TMT FE 500 as per IS 1786 for construction work. The vendor shall supply all necessary steel and 18gauge black annealed binding wire. Reinforcement steel bars are to be cut, bent, and tied per approved bar bending schedules and structural drawings, ensuring precise dimensions and placements. Steel bars shall be securely tied at all intersections using 18-gauge black annealed binding wire to maintain stability during concrete placement. Laps shall conform to MoRTH specifications and as directed in drawings, with no separate payment for laps or overlaps as per MoRTH Clause 1600. Proper clear cover shall be maintained with spacers and chairs as per drawings and CPWD standards. Steel will be measured by weight in kilograms, excluding binding wire and without allowances for overlaps or wastage. The scope of work includes supply, handling, and on-site quality assurance for positioning, alignment, and compliance with specifications and as directed by EIC. Safety measures and quality checks shall be implemented during all stages, ensuring high-	Kgs.	500.978	80.00	40078.22	

	standard reinforcement for structural integrity. Reinforcement bars from the approved make shall only be used.					
7	Providing and Applying 1 Coat Primer and 2 Coats of Weatherproof Paint of Asian or equivalent make All charges for the preparation and application of one coat of primer followed by two coats of weatherproof paint Asian or equivalent make of the approved shade to plastered surfaces. The surface must be thoroughly cleaned to remove dirt, dust, oil, grease, efflorescence, and any other contaminants that could affect the adhesion of the paint. The primer shall be applied first, followed by two coats of weatherproof paint, ensuring even coverage across the entire surface. The paint shall be applied at a coverage rate of 1 litre per 12 square meters for each coat. The work shall be carried out in accordance with MoRTH and CPWD specifications to achieve a durable, smooth, and uniform finish that protects the surface from weathering. The final price includes the cost of all materials (primer and paint), including transportation to the site, labor for surface preparation, cleaning, and application of the primer and paint in three coats (1 coat primer + 2 coats paint). It also includes machinery, tools, curing (if applicable), and all overheads and profit. Safety measures and quality checks shall be implemented during all stages. Relevant Standards: MoRTH Clause 800 (Painting and Surface Finishing Work) IS 15489:Code of Practice for Painting of Concrete Surfaces IS 5410: Specification for Weather-Resistant Paints for Exterior Use	Sq.m.	50.880	100.00	5088.00	
8	Fabrication & Installation of MS Staircase	Nos.	2	22000.00	44000.00	
				Total Amount	**252,928.722**	
				GST 18%	**45,527.170**	
				Grand Total	**298,455.892**	

We hereby confirm our acceptance of the terms and conditions of the tender and assure you of quality and timely completion of the work.

Looking forward to your kind consideration.

Yours Sincerely,

K Hazarika

ASOMI ENTERPRISE

K Hazarika,

Proprietor, Asomi Enterprise