Asomi Enterprise

Second Floor, H.No.3, Maya Path, Six Mile, Guwahati, 781022, Ph: 9706346509

Ref No.: *Date:*

To,
Team Procurement,
NHIT Eastern Projects Private Limited,
Dwarka, New Delhi – 110077

Subject: Submission of Quotation for Construction of Container Foundation at Galia Toll Plaza.

Respected Sir/Madam,

With reference to the above enquiry, we are pleased to submit our quotation for **Construction of Container Foundation at Galia Toll Plaza.**
The details are as follows:

Name of Project:- Kachugaon-Rakhaldubi Bus Junction-Kaljhar-Patacharkuchi at NH-27 Assam Road Projects

BILL OF QUANTITIES(BOQ) - of The New Porta Cabin For Galia Toll Plaza at ASSAM PROJECTS

Item No.	Description	Unit	Total Quantity	Tentative Rate	Tentative Amount	Remark
1	Excavation for foundation in earth, soil of all types, sand, gravel, and soft murmur, including removing the excavated material up to a distance of 50m, beyond the building area and stacking and spreading as directed, dewatering, preparing the bed for the foundation and necessary backfiling, ramming, watering including shoring and strutting etc. all complete.	Cu.m	13.650	400.00	5460.00	For Galia Toll Plaza, Foundation of Porta cabin (Conference cum Manager Room)
2	Backfilling of development area of Porta Cabin room for the depth of 2.5m with the approved borrow area material with all leads & lifts, transporting to site, spreading, grading to required slope and compaction to meet the requirement of table 300.2	Cu.m	54.000	490.00	26460.00	

3	All charges for supply & placing of Plain Cement Concrete (M-15 grade) in open foundations as per approved drawings and technical specifications, conforming to MoRTH Sections 1500, 1700, and 2200. The concrete shall be batched using a batch mix plant, ensuring uniformity and consistent quality. The mix shall use aggregates of size not exceeding 20 mm, with a workable slump suitable for PCC. The thickness of PCC shall be as specified in drawing. Concrete placement shall ensure a free-fall height of less than 1.5 m to prevent segregation, compacted using mechanical vibrators to achieve proper consolidation. The work includes the preparation of the foundation surface, leveling, placing concrete, and finishing exposed surfaces to achieve the required levels and smoothness. Adequate curing, as per approved methods, shall be carried out for at least 7 days to attain the desired strength. Sampling and testing shall follow relevant IS codes, including IS 456 and IS 516, to ensure compliance with quality standards. The rate shall include all costs associated with labor, material, machinery,batching,transporting,placing,compactin g, curing, sampling, testing, and incidental works. Shuttering costs, where required, are also deemed included in the rate of PCC. The work shall be executed with due diligence, adhering to environmental and safety measures, and ensuring compliance with the project's specifications and MoRTH standards.	Cu.m	2.290	5250.00	12022.50	
4	1st Class Brick Masonry Work in Cement Mortar 1:3 This item includes the construction of brick masonry using 1st class burnt clay bricks, laid in cement mortar of mix ratio 1:3 (Cement: Sand), for foundations, walls, piers, columns, and other structures as per the approved drawings and technical specifications, from ground level till plinth and in superstructure above plinth level up to floor one level. The work includes thoroughly soaking the bricks in water for a minimum period of one hour prior to laying them to ensure proper bonding and to achieve maximum strength. The work shall also involve the protection of the green structure from rain during curing by suitable coverings. Curing of the masonry shall be done for a minimum period of 7 days as per standard practices to ensure the proper hydration and strength development of the mortar and masonry. The work excludes the cost of pointing, plastering, or any additional finish unless specified otherwise. The work shall be executed in accordance with the relevant CPWD and IS specifications. The final price includes the cost of procurement of 1st class bricks, cement, sand, and other necessary materials, including royalty charges, transportation to site, soaking of bricks, labor, machinery, curing, and all overheads and profit. The cost does not include pointing, plastering, or	Cu.m	6.900	9500.00	65550.00	

	any decorative finishes unless specified separately. Safety measures and quality checks shall be implemented during all stages. Relevant Standards: CPWD Specification No. 6.4 (Brick Masonry Work) MoRTH Clause 1300 (Brick Masonry Work)					
5	Reinforced Cement Concrete (M25) in foundations All charges for providing and placing RCC M25 grade concrete for foundations as per approved drawings and technical specifications, conforming to MoRTH Sections 1500, 1700, and 2200. The concrete shall be produced using a batch mix plant, transported via transit mixers, and placed in position using appropriate equipment. The mix design, including approved admixtures, shall be submitted for approval by the Engineer-in Charge (EIC) before production. Aggregates shall not exceed a maximum size of 20 mm, and the concrete shall have a workable slump suitable for RCC. Concrete placement shall ensure a free-fall height of less than 1.5 m to avoid segregation and be compacted using mechanical vibrators for proper consolidation. The rate includes all formwork/shuttering costs to support concrete placement, which must ensure safety and stability. Adequate curing shall be performed for at least 7 days, following approved methods, to meet specified strength and durability. Quality control measures include sampling, testing, and certification as per IS codes like IS 456 and IS 516 to verify strength and compliance. Environmental, material handling, and safety protocols shall be adhered	Cu.m	7.236	7500.00	54270.00	
6	Reinforcement Steel: All charges for providing, cutting, bending, transporting, and tying reinforcement steel of designation TMT FE 500 as per IS 1786 for construction work. The vendor shall supply all necessary steel and 18gauge black annealed binding wire. Reinforcement steel bars are to be cut, bent, and tied per approved bar bending schedules and structural drawings, ensuring precise dimensions and placements. Steel bars shall be securely tied at all intersections using 18-gauge black annealed binding wire to maintain stability during concrete placement. Laps shall conform to MoRTH specifications and as directed in drawings, with no separate payment for laps or overlaps as per MoRTH Clause 1600. Proper clear cover shall be maintained with spacers and chairs as per drawings and CPWD standards. Steel will be measured by weight in kilograms, excluding binding wire and without allowances for overlaps or wastage. The scope of work includes supply, handling, and on-site quality assurance for positioning, alignment, and compliance with specifications and as directed by EIC. Safety measures and quality checks shall be implemented during all stages, ensuring high-	Kgs.	500.978	80.00	40078.22	

	standard reinforcement for structural integrity. Reinforcement bars from the approved make shall only be used.					
7	Providing and Applying 1 Coat Primer and 2 Coats of Weatherproof Paint of Asian or equivalent make All charges for the preparation and application of one coat of primer followed by two coats of weatherproof paint Asian or equivalent make of the approved shade to plastered surfaces. The surface must be thoroughly cleaned to remove dirt, dust, oil, grease, efflorescence, and any other contaminants that could affect the adhesion of the paint. The primer shall be applied first, followed by two coats of weatherproof paint, ensuring even coverage across the entire surface. The paint shall be applied at a coverage rate of 1 litre per 12 square meters for each coat. The work shall be carried out in accordance with MoRTH and CPWD specifications to achieve a durable, smooth, and uniform finish that protects the surface from weathering. The final price includes the cost of all materials (primer and paint), including transportation to the site, labor for surface preparation, cleaning, and application of the primer and paint in three coats (1 coat primer + 2 coats paint). It also includes machinery, tools, curing (if applicable), and all overheads and profit. Safety measures and quality checks shall be implemented during all stages. Relevant Standards: MoRTH Clause 800 (Painting and Surface Finishing Work) IS 15489:Code of Practice for Painting of Concrete Surfaces IS 5410: Specification for Weather-Resistant Paints for Exterior Use	Sq.m.	50.880	100.00	5088.00	
8	Fabrication & Installation of MS Staircase	Nos.	2	22000.00	44000.00	
				Total Amount	**252,928.722**	
				GST 18%	**45,527.170**	
				Grand Total	**298,455.892**	

We hereby confirm our acceptance of the terms and conditions of the tender and assure you of quality and timely completion of the work.

Looking forward to your kind consideration.

Yours Sincerely,

K Hazarika

ASOMI ENTERPRISE

K Hazarika,

Proprietor, Asomi Enterprise